# Optical Access Technology and Architecture Considerations for CATV Networks

Cate McNaught Market Development, Carrier Networks August 16 2018


catherine.mcnaught@corning.com

# Agenda

- Fiber Basics
- FTTH Overview
- Architectures
- SFU
- MDU

### History – How it Came to Pass?

48 years ago three Corning scientists created the first low loss optical fiber






Optical fiber was invented by:


- Dr. Donald Keck,
- Dr. Peter Schultz
- Dr. Robert Maurer

### History – How it Came to Pass?

### David Colladon Guided Light Experiment




### *History – How it Came to Pass?* Failed Attempt to Light a Building = Fiber Optics



• William Wheeler patented a scheme for piping light through buildings.

 Wheelers light pipes probably wouldn't have reflected enough light to do the job. However, his idea of light piping reappeared again and again until it finally coalesced into optical fiber

# *History – How it Came to Pass?* The Sequence




### CORNING

#### **Transmission Sequence**

- 1. Information is encoded into electrical signals
- 2. Electrical Signals are converted to digital or analog signals that modulate a laser.
- 3. Light travels down the fiber
- 4. A detector changes the light signals into electrical signals
- 5. Electrical signals are decoded into information

### *The Science* How Does it Work?




Total internal reflection: Encoded into a pattern of light waves, information travels through each optical fiber

The <u>waves</u> move through the fiber from a given source to a destination such as an **O**ptical **N**etwork **T**erminal where it is then decoded.

The goal: Trap the light in the fiber and keep it there.

### *The Science* Electromagnetic Spectrum

### Wavelength: The distance between identical points on a wave (nanometers or nm)




#### **Operating Wavelengths:**


- 850 nm = Short Wave Multimode
- 1300 nm = Long-Wave Multimode
- 1310 nm = Traditional Standard Single-mode
- •1490 nm = FTTx (Downstream Data/Voice)
- 1550 nm = Long-Wave Single-mode
- 1625 nm = Extra Long-Wave Single-mode (WDM)

# PON Technology Wavelengths


Wavelengths selected by Standards bodies to support co-existence




# FTTH – Generic Component Layout



### Some observations on trends and convergence




## Market & Technology Trends: Wireless Access as a Natural Complement to FTTx



# FTTH cost for US benchmark

Cost Highly Dependent on a Few Deployment Factors




\* Underground labor/deployment is 2-3 x higher cost than aerial

### CORNING

\*\*SFU is typically 25% higher cost than MDU


#### FTTH learning curves

All FTTP deployments have experienced learning curve cost improvements




#### - Fixed cost allocation over a larger passed HH base

# FTTH – Total Cost Equation



equipment suppliers reduce network component/solution costs

# Central Switch Homerun (CSH)



#### **Benefits**


- Dedicated optical path to subscriber
- All switching and/or splitting at central
   point
- Highest bandwidth capacity and adaptability
- System admin from one location

### CORNING

#### Cost Considerations

- Additional up-front capital investment
- Fiber-rich F1 and F2 system
- CO/HE real estate

# Local Convergence (LC)




#### **Benefits**

- Fiber lean feeder (F1) and fiber-rich distribution (F2) system
- Ability to transition to point-to-point with F1 upgrade
- Provides dedicated optical path from LCP to subscribers

#### **Cost Considerations**

• Requires truck-roll to LCP for splitter connection / management

# Distributed Splitting (DS)



Minimal up-front network CAPEX requirements

 No single splitter configuration or adaptation point

- More complex system


administration

# Architecture and Deployment Considerations




# Take Rate


- The percent of homes passed that subscribe and generate revenue for provider
  - Anticipated take rates initially and over time impact investment / CAPEX decisions



# **PON Benefits**



# **Product Application Areas**



# Head End


- Location of originating electronics
- Can also be located in hut, cabinet or node

### **CSH** architecture

- Manage both splitters and distribution fibers in rack
- Potentially large number of fibers
- Maximize OLT / splitter port usage


### LC / DS / SS architectures

- No splitters in HE
- Smaller number of fibers than CSH



# Feeder (F1) Cable


- Located from HE to Local Convergence point
- Minimal mid-spans compared to F2 cable
- CSH architecture
  - High fiber counts
- LC, DS, SS architectures
  - Mid to low fiber counts






# Local Convergence Point

- May be splice point or cross-connect cabinet in CSH architectures
- Houses splitters in LC, DS and SS architectures
- Connectors provide for easy adds, drops, changes








# **Distribution (F2) Cable Products**

- Brings fiber from convergence point to locations near homes
- Cable accessed multiple times
  - Higher fiber count designs may make access more difficult
  - Typically loose tube cable for ease of access
- Pre-terminated cable options available
- Can use same cable types as feeder cables
- Aerial / buried / duct installations
- All dielectric or armored





# **Distribution Cable**

- Bulk Cable
- Pre-terminated FlexNap<sup>™</sup> cable
  - Supports fast deployment of network reduces access and splicing in field
  - Tap placement customized based on specific requirements
  - "The design is marked on the cable" locations IDs, fiber assignments at locations, terminal count, tap and tether #, slack
  - System generated splice plan for each cable
  - Allows deferment of drops and multiports





Network Access Point (NAP)

- Splice terminals
- Multiports
- Taps included in pre-terminated FlexNap cables








# Connecting to the ONT

- Outdoor ONT
  - Direct connection from drop cable
- Indoor ONT
  - Transition between outdoor and indoor drops
- Indoor / outdoor drop cable
  - Eliminates transition requirement









SFU Design and Cost Considerations

# **Overview of Design Process Steps**

"Start from homes and work back"




• Bring NAPs together by determining splice points

- Decide on optimum cable paths to link splice points
- Bring cables to convergence point(s)
- Select convergence products(s)
- Determine feeder cable size and path
- Provide hardware for HE


Impact of Crossing Street with Drops

- Typically requires shorter drop lengths
- Reduces number of lot crossings
- Installation requirements have big impact
  - Trench, pull or bore across lot or street




Model Assumptions

# Drop Length Impact (crossing vs. same side of street)




# Lot Front Distances

- Larger lot fronts require longer drops
- Cost of longer drops and to install drops might outweigh savings gained from larger NAP size
- Dense areas may benefit from large NAP size






# Street front vs. Back lot



# Sample Design – NAP Placement




# 4-port Multiport (# HP)Wiring limits

## **Determining Cable Access Points**


Factors to consider

- Impact on deployment speed
- Physical cable access
  - Slack cable placement / requirements
  - Products needed to store splice product and extra cable
- Cable paths
- Fiber splicing
  - Setup cost
  - Per splice cost
- Product costs
  - Different products required for different splicing strategies
- Product inventory impacts
- CORNING

### Cable Access Points – One Side of Street




### Access Cable at Each NAP Point



- Considerations
  - Three cable midspans
    - Splice setup time and charges
    - · Cable fiber count impacts ease of accessibility
    - Additional slack / slack storage
  - Three splice closures / terminals / multiports


### Access Cable at Single Point




- Considerations
  - One cable midspan
    - Decreases splice setup time and charges
    - Reduces slack / slack storage
  - Requires multiport tail installation
    - Installed with distribution cable or separately
    - May be able to be deferred
    - May require additional per-foot charges
    - Can be significant based on multiport tail lengths

FlexNAP<sup>™</sup> System

- Replaces splice points with factory installed tap
- Allows deferment of multiport




Splicing – Access Cable and Cross Street




- Considerations
  - Three cable midspans
  - Multiport tail installation for 2<sup>nd</sup> multiport
  - Cost to install across street

## FlexNAP<sup>™</sup> System – Access Cable and Cross Street




- Decision Factors
  - Cable midspans eliminated
  - Ability to defer local multiports
  - Additional cost for three pre-installed taps
  - Multiport tail installation for 2<sup>nd</sup> multiport
  - Cost to install across street

### Spliced Cable – Access Cable at One Point



- Considerations
  - One cable midspan
  - One street crossing
  - Costs to install multiple multiport tails

## FlexNAP<sup>™</sup> System – Access Cable at One Point




- Considerations
  - Cable midspan eliminated
  - Single street crossing
  - Ability to defer local multiports
  - Costs to install multiple multiport tails

## Sample Design – Multiport Tails and Splice Points



## Sample Design - Cable Paths



## Sample Design – LCP Placement



### Sample Design – FlexNap Cable




## **Three Basic Solution Families**


Evaluated Against Large-Scale Deployment Challenges

	Capex/ Opex Equation	Speed / Cost of Installation	Optimal Subscriber Density	Level of Risk assumed	Optimal Method of build
Full Splice	\$ Take Rate	<ul> <li>Fast planning</li> <li>Slow first install</li> <li>Slow subscriber connection</li> <li>\$\$\$ Labor</li> </ul>	Low to Medium	Moderate to High	Aerial, Duct, Plow, Trench
Semi Splice	\$ Take Rate	<ul> <li>Medium planning</li> <li>Slow first install</li> <li>Fast subscriber connection</li> <li>\$\$ Labor</li> </ul>	Low to High	Moderate	Aerial, Duct, Plow, Trench
Light Splice	\$ Take Rate	<ul> <li>Detailed planning</li> <li>Fast first install</li> <li>Fast subscriber connection</li> <li>\$ Labor</li> </ul>	Medium to High	Low	Aerial, Duct (others possible but less common)


Total Cost Curve: Full Splice




# Total Cost Curve: Semi-Splice








### **Total Cost of Ownership**





### **Optimization Around Subscriber Density**




## Time Savings Enabled by Optimized Solutions

	Cable Placement	Splicing	Testing and QC	Whole Service Area
	Cable placement footage reduction of <b>10% to 20%</b>	Splicing time reduction of <b>50% to</b> <b>70%</b>	Testing and network QC reduction of <b>50%-</b> <b>70%</b>	Total Design Area Build Time Reduction of slightly over <b>3x</b>
	Example: Cable pull reduced from 3 days to 2 days	Example: Splicing time per build reduced from 5 days to 2 days	Example: One day of testing reduced to 2-4 hours	Example: Complete LCP service area reduced from 20 days to 6 days
CORNING		requced from 5 days to 2 days		area reduced from ZU days to 6 days

## MDU Demographics: **Building Size**



< 3 Floors; 12 Living Units



< 6 Floors; 72 Living Units






■ Large High-rise 7 Stories

### **MDU** Application Spaces

- Splitter Cabinet (Outdoor or Indoor)
- 2 Riser Cable
- **3** Floor Distribution Terminal (FDT)
- 4 Horizontal Drop Cable
- **5** Premise Connection Point




## Challenges in the MDU Space

- Unique access, distribution and routing challenges in every building
  - Infrastructure planning for every MDU
  - Fiber pathways cannot always be hidden
  - Various building sizes/architectures require different solutions
- Existing ducts are full, unusable, not continuous
- Limited space in the basement and in the floors for hardware and cable management
- Negative impact on tenants during install
- Timing gaining builder/owner permits, then quickly completing the installation
- Working with or around other contractors



### **MDU Deployment Options**



CORNING

NOTE: Assessments based on Corning models, field trials and deployments.

### **MDU Solutions Summary**

	Full-Precon Solutions	Semi-Precon Solutions	Full-Splice Solutions	
	2			
Speed of Deployment	Fast	Moderate	Slow	
Subscriber Connection	Fast	Moderate	Slow	
Type of build	High to Mid-rise	Mid to Low-rise	All	
Design verification/planning	High	Moderate	Low	
Level of Risk	Low	Moderate	Moderate to High	
Splices in the field	Splices in the field Low		High	
Labor Skill Level	Labor Skill Level Low		High	
Deferability High		Moderate	Low	
CORNING				


### CATV Node Assembly Distribution Child Parent W/MTP XWDM Frame ТΧ Node Node Тар Home **OSP** Cable **OSP** Cable . . Μ M D CATV CO Splice Closures Node XWDM Vault Splice Jumper Jumper Assembly SST Ribbon UCAO Splice **RF** Drop Cables REG LCPE Connectors Closures SCAPC CATV Node Closures MiniXtend® **Eclipse**® Jumper OSE Microduct Assembly Frames Eclipse® **Optical Splice** Cables WDM Enclosure **ALTOS®** Modules SCF Splice **Eclipse**® Aerial Closures Gen3 **Broadband Trunk** Housings + Duct Cables Splitters and Distribution JIB ALTOS Connectors CATV Node OSE Jumper-in-Figure-8 Assembly (Hybrid) Splice Trays a-Box Cable Centrix™ Centrix™ CamSplice™ Splitter + WDM Mechanical Splice SOLO® Frames CATV Node I ap with Cassettes Cable SCF Splice Assembly (W/MTP) True Split Technology Attenuators Closures Centrix™ Housings CORNING

CATV Network Solutions

N+X, N+0, FTTH



catherine.mcnaught@corning.com



## Our Mission:

Another 165 years of Innovation and Independence...

...and a world that is better because of our efforts

CORNII

© 2017 Corning Incorporated